Workshop on Radiation Exposure Control at TEPCO's Fukushima Daiichi Nuclear Power Plant, etc.

> Introduction of Examples for Reducing Exposure Dose during the Decontamination at the Reactor Building (Fukushima Daiichi Nuclear Power Plant Unit 3)

Maintenance Technology Section

**Construction and Maintenance Engineering Department** 

Nuclear Energy Systems Division Mitsubishi Heavy Industries, Ltd.

November 2015 Mitsubishi Heavy Industries, Ltd.

#### **MHI PROPRIETARY CLASS B**

This document contains information proprietary to Mitsubishi Heavy Industries, Ltd. (MHI); it is submitted in confidence and is to be used solely for the purpose for which it is furnished.

This document and such information is not to be reproduced, transmitted, disclosed or used otherwise in whole or in part without authorization of MHI.




Activities toward decommissioning have been promoted at the Fukushima Daiichi Nuclear Power Plant. However, the dose rate inside buildings, especially in the reactor building, is still high, and decontamination works by human workers are not realistic.


Under the initiative of the Ministry of Economy, Trade and Industry (METI), the MHI has implemented the national project "Development of Remote Decontamination Technology in the Reactor Building", and <u>has</u> <u>developed a remote decontamination robot.</u>

The MHI employed the developed decontamination robot at the Unit 3 reactor building. This presentation introduces examples for reducing exposure dose during the decontamination.

In order to reduce the dose rate in the Unit 3 reactor building, dust suction and **rubble removal** were both conducted on the floor.



Developed as a work robot with double arms, utilized in both <u>the contamination survey</u> and <u>decontamination</u> in 1F (at the reactor building).




★三菱重工


MHI Technical Document: Class B

#### **Overview of the work** [Prodedures]

- Preparation / preliminary maintenance
  Placement of equipment in front of Unit 3 [high dose rate]
- ■③ Dust suction [high dose rate]
- ■④ Changing the tool
  - (Suction  $\Rightarrow$  Recovery of rubble)
- Secovery of rubble [high dose rate]
- ■⑥ Post-maintenance/ clearance



#### MHI Technical Document: Class B



© 2015 MITSUBISHI HEAVY INDUSTRIES, LTD. All Rights Reserved.

### [Major causes of radiation exposure]

① It was necessary for the workers to support the cables and hoses, due to difficulty in full remote operation, whenever the equipment was moved inside the building.


## [Measure]


- Transport of decontamination equipment into and from the reactor building, limited to Mondays and Fridays, respectively, rather than every day. ⇒Reduction in the work load of the workers for the cables and hoses.
- Coordination ①: Impossible to close the door after the work because of the cables and hoses of the equipment passing the door of the reactor building. Adjustment made to enable the work with the door slightly open all through the day.
- Coordination ②: Decision made for the equipment to be stored inside the reactor building, taking into account the estimated failure risks from the knowledge obtained from past test results and literature, etc. with the understanding of increase in failure risks due to accumulation of radiation.

The method of operation was modified to store decontamination equipment around the decontamination area inside the reactor building.

After the measure

⇒ Resulting in no supporting works for the cables, leading to reduction in daily radiation exposure.






MHI Technical Document: Class B

6





#### Supporting hoses





A suction hose and the wheeled platform

Supporting hoses required during the work is a cause of radiation exposure.

Development and utilization of wheeled platforms to relieve the work load for workers supporting the hoses, etc.

## [Major causes of radiation exposure]

②A shielded hut (only vertical sides shielded) constructed for temporary use aimed at radiation dose reduction for workers at the site, less effective due to gamma rays from all directions (from beneath the floor, vertical sides, and above the building).

## [Measure]

⇒ <u>A box culvert</u> placed near the work area (constructed by Company K), borrowed from K, <u>used as the common rest facility for workers.</u>


Coordination ①: The rest facility constructed by K to be <u>in common use</u> for staff of TEPCO as well as related parties.

Coordination ②: Daily work plans, adjusted between the MHI and Company K to avoid time schedule conflicts for the efficient use of the culvert.



2/2

#### Use of the box culvert




The box culvert in use in the neighboring work area, to be in common use as the rest facility for workers.

#### **Exposure reduction effect**

🙏 三菱重工

MHI Technical Document: Class B



- Measures have been implemented for reducing exposure dose during the decontamination works on the first floor of the Unit 3 reactor building in the Fukushima Daiichi Nuclear Power Plant.
- Decontamination equipment has been stored inside the reactor building during the work with an assessment of failure risks. Exposure has been reduced to radiation that would be received during transport of equipment into and from the reactor building.
- Improvement of efficiency in radiation exposure reduction by <u>using a common</u> rest facility with other companies working at the site.
- <u>It is important</u>, when conducting works in areas of high radiation outside the reactor building, <u>to establish a coordination framework</u> under the guidance of TEPCO <u>where information on the rest facilities and areas of low radiation is</u> <u>mutually shared while such facilities and areas are used as common areas.</u>

# MITSUBISHI HEAVY INDUSTRIES, LTD.

## Our Technologies, Your Tomorrow

© 2015 MITSUBISHI HEAVY INDUSTRIES, LTD. All Rights Reserved.