

Workshop on Radiation Exposure Control at TEPCO's Fukushima Daiichi Nuclear Power Plant, etc.

Activities Concerning Radiation Control for the Treatment of Accumulated Water at the Fukushima Daiichi Nuclear Power Plant

10 November 2015

Yasutaka Miyajima Nuclear Plant Radiation Protection Management Section Department of Nuclear Service Department Hitachi-GE Nuclear Energy, Ltd.



[Contents]

- 1. Introduction
- 2. Overview of the treatment of accumulated water
- 3. Issues and challenges for the treatment of accumulated water
- 4. Exposure dose reduction measures for key persons
 - 4.1 Individual dose control
 - 4.2 Measures for exposure dose reduction
 - 4.3 Outcomes of exposure dose reduction measures for key persons
- 5. Measures to prevent problems related to radiation control
- 6. Summary
- 7. Challenges for the future
- 8. Conclusion

1

1. Introduction

нітасні 🛞

Radiation exposure and major works at 1F

CST: Condensate Storage Tank SFP: Spent Fuel Pool



Treatment of Accumulated Water: Installation of a pumping system for accumulated radionuclide-contaminated water.

against Accidents in Power Reactors, etc. – Fiscal Year 2012 (Technology Development of Swimming Survey Robots toward Advancement of the Foundations for Remote Technologies)



Overview ① Objective and details of the works

Objective	Prevent leakage of the accumulated water from the building, by controlling the water level of accumulated water in the building, against the decline in the groundwater level due to installation of the frozen-soil impermeable walls.
Details of the works	Installation of pumps and water level gauges in the reactor buildings as well as the relevant installation of pipes and cables, and drilling the floor.
Working period	Required to complete before the establishment of the frozen-soil impermeable walls. Initial schedule: from the end of October 2014 to the end of March 2015 (subject to change)





2. Overview of the treatment of accumulated water

Overview 2 Work areas and dose rate





Issues and challenges

Works conducted in a large-scale setting and in areas of high radiation, requiring responses to the following two challenges.

1) There is a concern that the key persons who have already received a large cumulative exposure dose may not be able to continue engaging in the works at 1F during and after the treatment period as they will have reached the exposure dose control limit.

Measures are required to reduce the exposure dose of key persons at 1F.

2) There is a concern that problems related to radiation control may occur for workers newly engaging in the treatment, among whom there would be many without any previous work experience at 1F or other nuclear facilities.

Measures are required to prevent problems related to radiation control.

Key persons

Those workers are exceptional who have thorough knowledge about specific situation at the site of 1F such as "environment", "operation", "equipment", and "layout", etc. among those engaging in works before and after the earthquake.





ontrol limit for	individual dose		(mSv)		
Period (Fiscal year)	Dose limit (Ionizing Radiation Ordinance)	Control limit set by Hitachi-GE			
(Fiscal year)		1F	Other plants		
5-year *	100	90			
1-year	50	45	20		

<u>5-year control limit and the control target value for the treatment</u> (Fiscal year) 2013 Until 2011 2012 2014 2015 2016---2010 exposure dose from emergency works in March 2011 3.11 included, following a administrative notification Subsequent Current 5-year control period (Control limit: 90 mSv) 5 years Preceding Period in which the treatment was conducted. 5 years Target value for cumulative exposure dose: 70 mSv 20 mSv Control limit reserved for Exposure dose from Exposure dose from the treatment fiscal year 2015 emergency works in of accumulated water. March 2011 (about the value of annual control limit)

7



Cumulative exposure dose by workers: before the treatment (for supervisors)

Before the treatment, cumulative exposure dose since Fiscal Year 2011 (as of the end of Sep. 2014)



Cumulative exposure dose, exceeding or reaching 70 mSv for key persons



<u>Cumulative exposure dose by workers: after the treatment (expected for supervisors)</u>



Cumulative exposure dose, exceeding 70 mSv at the end of FY 2014 for more than half of key persons.

This would have an impact on works both during the treatment and for the fiscal year 2015.

9



<u>Cumulative exposure dose by workers: after the treatment (expected for group leaders)</u> Assuming that all workers receive uniform doses from the treatment (+22 mSv/worker)



Cumulative exposure dose, exceeding 70 mSv for many group leaders as well.

HITACHI 🛞

Measures against challenges



4.1 Individual dose control

Control method (previous)





4.1 Individual exposure dose control

Control method (previous)





Control method (in this treatment)



: Newly implemented

4.1 Individual exposure dose control



Control method (implemented)

Daily confirmation of cumulative exposure dose for each worker

Managed not only with a system but also by each subcontractor



Dose control of 70 mSv, achieved at the end of Fiscal Year 2014 by frequent confirmation and instruction



Exposure dose reduction measures are required with respect to the environment to reduce the exposure dose for key persons

Drastic measures are also required especially in areas of high dose rate

Measures related to specification and methods of construction,

in addition to decontamination and shielding

4.2 Measures for exposure dose reduction

① Implementation of exposure reduction measures (reduction by design modification)

Change of piping routes at the Matsuno-roka (corridor) in T/B of Unit 1



Possibility of significant exposure reduction from the removal of interfering objects by making a detour for the piping route to pass areas of low dose rate

4.2 Measures for exposure dose reduction

① Implementation of exposure reduction measures (reduction by design modification)

Change of piping routes at the Matsuno-roka (corridor) in T/B of Unit 1

Study on the effect of changing the route

Exposure dose reduction, expected to be 400 man-mSv or more

Effects expected to be large

Changing the route, consideration of design change

Design change feasible

Implementation



Significant exposure dose reduction. Reduced by about 510 man·mSv.

4.2 Measures for exposure dose reduction

(2) Implementation of exposure reduction measures (reduction by improving methods)

Remote monitoring of NW area of R/B in Unit 1

Up to 1.3 mSv/h

HITACH



Reduced by about 90 man·mSv: significant reduction of exposure for supervisors

19

③ Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Decontamination/shielding at the NW area of the R/B in Unit 1



(mSv/h)

4.2 Exposure dose reduction measures

③ Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Decontamination/shielding at the NW area of the R/B of Unit 1



(mSv/h)

: Shielding (2- to 4-fold lead with 3 mm thickness)

③ Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Decontamination/shielding at the NW area of the R/B of Unit 1



(mSv/h)

: Shielding (2- to 4-fold lead with 3 mm thickness)

③ Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Decontamination/shielding at the NW area of the R/B of Unit 1



: Shielding (2- to 4-fold lead with 3 mm thickness)

Significant reduction of the exposure dose rate in he area

Reduction rate: about 1,800 man·mSv

(3) Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Decontamination of the NW area (before and after decontamination)





Before decontamination



After decontamination © Hitachi-GE Nuclear Energy, Ltd. 2015. All rights reserved.



③ Implementation of exposure reduction measures (reduction of dose rate by shielding, etc.)

Shielding of the NW area in the R/B





(4) Exposure reduction measures (reduction by other measures)

Visualization of radiation environment (by indication with rotating beacon lights)

Reflection of a request by workers.



Significantly effective in preventing excess exposure in addition to exposure reduction.



Results of exposure reduction measures

Reduction achieved by the major measures

Major exposure reduction measures	Man·mSv
1 Change of the piping route at corridor in T/B of Unit 1	510
② Remote monitoring of NW area in R/B of Unit 1	90
3 Shielding and decontamination of NW area in R/B of Unit 1	1,800
Other measures (shielding, improvement of methods, etc.)	1,600
Reduction by implementation of measures (sub-total)	4,000
Reduction by modification of construction specifications, etc.	3,600
Total	7,600

Achievement of 4,800 man·mSv (as of 31 May) compared with the initial expectation of 12,400 man·mSv.

Significant reduction achieved for the exposure dose.

Individual exposure dose reduced for key persons as well.

4.3 Outcomes of exposure dose reduction measures for key persons **HITACHI**

Achievement after the treatment (for supervisors)

After the treatment. Cumulative exposure dose since Fiscal Year 2011 (as of the end of Fiscal Year 2014)

5-year control limit: 90 mSv



The allowable exposure dose for works in Fiscal Year 2015 has been reserved for key persons in accordance with the 5-year control limit owing to the results achieved by the individual dose control and the exposure reduction measures.

28

4.3 Outcomes of exposure dose reduction measures for key persons **HITACHI**

Achievement after the treatment (for group leaders)

After the treatment. Cumulative exposure dose since Fiscal Year 2011 (as of the end of Fiscal Year 2014)



Similarly, the allowable exposure dose for works in Fiscal Year 2015 has been reserved for key persons among the group leaders.

5. Measures to prevent problems related to radiation control



Workers with or without previous work experience at 1F or other nuclear facilities



<u>Physical experience education \rightarrow </u>

<u>The hands-on "experience education of radiation</u> <u>control related to dangers" was developed.</u>



The "experience education of radiation control related to dangers" - 1

Experience of body contamination

Recognizing contamination with fluorescent paints representing contamination, by irradiating with black light.

Experiencing surface contamination when assistance is or is not available in wearing and removing the protective clothing.



Experience of APD alarm sound

Experiencing the APD alarm sound, which is unusual in daily life, using an APD demonstration device.

Experiencing how the alarm sound is heard in the presence or absence of noise.



APD: Alarmed Pocket Dosimeter



The "experience education of radiation control related to dangers" - 2

Experience of exposure dose reduction

Use of natural a radiation source

- Dose reduction with respect to distance from the source
- Dose reduction by shielding



Experience of checking for full-face mask leaks

- Use of a mask and the fit checker
- Check for fitness of the mask
- Experiencing leaks when fitting of the mask





Effects and results of the "experience education of radiation control related to dangers"

Provided a total of 5 times to 184 workers.

Workers' improved comprehension, confirmed by questionnaire results after the education experience



No ("zero") problem has occurred related to radiation control owing to "experience education of radiation control related to dangers" and other activities to prevent problems.

6. Summary

- HITACHI 🋞
- By administrative measures including the setting of a target value of the dose control for each of the workers taking into consideration of their 5year cumulative exposure dose as well as staff deployment coordination, etc. and

measures with respect to the environment including decontamination, shielding, and specification and methods of construction,

the key persons may be able to continue engaging in both the current works and those for the Fiscal Year 2015 at 1F while controlling their exposure dose at 1F.

 By providing the "experience education of radiation control related to dangers",

no ("zero") problem has occurred related to radiation control.



1) Keeping and training of key persons

It is an important challenge to keep and train personnel to be key persons at the site in the long-run 1F decommissioning works.

2) Preventing problems related to radiation control

Continued preventive measures are required through provision of education to newly engaging workers as well as further improvement in comprehension of radiation control.

8. Conclusion



• Steady progress has been made in the works related to the treatment of contaminated water owing to the progress in the treatment of accumulated water and the operation of the Advanced Liquid Processing System, etc.

•Works toward the 1F decommissioning are being implemented, such as the understanding of the situation by use of robots in investigating inside PCV of Unit 1.

•Toward the 1F decommissioning, the works are planned from now on to be conducted in high dose rate areas.

The radiation control activities, such as individual dose control and measures for exposure dose reduction, will become even more important.



The Hitachi group is committed to the works for the decommissioning of Fukushima Daiichi Nuclear Power Plant.

