

Commissioned by the Ministry of Health, Labour and Welfare in FY2016
Project to Enhance the International Transmission of Radioactivity-Related Information
on the Workers at TEPCO Holdings' Fukushima Daiichi Nuclear Power Plant

Good Practices in Radiation Exposure Dose Reduction Measures



1F-Unit 3 Reactor Building 5F State Immediately After the Accident




1F-Unit 3 Reactor Building 5F Conceptual Illustration of the Fuel Removal Framework as

Source: Kajima Corporation

Principles for Radiation Exposure Protection

(1) Reducing external exposure



To reduce **external exposure**, it is important to understand the following four principles of radiation exposure protection

<p>Principle 1 Remove radioactive materials</p> <p>Move radioactive materials or wash out them from the inside of piping (flushing).</p> 	<p>Principle 2 Maintain sufficient distance from radiation</p> <p>If possible, move away from the radiation source and do not get any closer to it than required (also remember where the waiting areas are).</p> 
<p>Principle 3 Install shielding</p> <p>Cover radioactive equipment, piping and others with shielding materials such as leadwool or lead plates.</p> 	<p>Principle 4 Reduce working time</p> <p>Ensure sufficient preparation before conducting work, such as discussing procedures involved or inspecting tools so that work proceeds smoothly.</p> 

(2) Preventing internal exposure

To prevent **internal exposure**, it is important to wear the required personal protective equipment so that radioactive materials are not taken into the human body

Measures also need to be put in place to prevent radioactive materials from being blown around in the air, as well as to contain (and limit) any contamination and stop it spreading (dispersing).

<p>Principle 1 Wear protective equipment</p> <p>Wear the required personal protective equipment and fit the respiratory protective equipment properly so that there are no leaks in.</p> 	<p>Principle 2 Utilize equipment and materials</p> <p>For work where there is the risk of dust being blown around, utilize temporary shelters or exhaust fans.</p> 
<p>Principle 3 Move to safety</p> <p>Move to a non-contaminated area immediately in the case of injury.</p> 	<p>Principle 4 Clearly outline contamination zones</p> <p>Clearly outline contamination zones and ensure full control and management of access to the zone. Cover any objects being taken out of the contamination zone with a sheet or similar material to prevent spreading (dispersing) contamination.</p> 

1F Site Zoning Area Control

(1) 1F Site Zoning Area Status


Condition		Zone	Protective Equipment
Control Zone	Areas Requiring Full-face/Half-face Mask	Red zone (Anorak areas) • Inside unit 1 to 3 reactor buildings • Areas with stored water around unit 1 to 4 reactor buildings	• Full-face mask • 2 layer coverall or anorak • Work boots (for R zone) • Helmet (for R zone) • Cotton gloves + rubber gloves
		Yellow zone (Coverall areas) • Inside buildings that include water treatment facilities (such as desalination units, multi-nuclide removal facilities)*1 • Work in areas around tanks that contain concentrated salt water, strontium-treated water*2, and work that involves the handling of transport lines to tanks	• Full-face mask + coverall • Work boots (for Y zone) • Helmet (for Y zone) • Cotton gloves + rubber gloves
		• Around unit 1 to 4 buildings (4 m/10 m circle) • Specified as required to suit work environment (such as inside unit 5, 6 building, parts of storage areas for high-radiation exposure dose rubble)	• Half-face mask, • coverall • Work boots (for Y zone) • Helmet (for Y zone) • Cotton gloves + rubber gloves
	Area Not Requiring Full-face Mask	Green zone (Regular uniform areas) Areas excluding the above	• DS mask • Site clothing, regular work clothing*3 • Work boots (for G zone) • Helmet (for G zone) • Cotton gloves + rubber gloves or work gloves
Control zones with no Risk of Contamination	• Inside important anti-seismic buildings and inside rest areas		

*1: Excludes observations and other operations that are not considered work.

*2: Excluding work that does not involve the handling of concentrated salt water, patrolling, field surveys in the work planning phase, observation visits, etc.

*3: Certain light work (such as patrolling, monitoring and transportation of items brought in from outside the premises).

(2) 1F site area map



* When working with highly concentrated dust (such as demolishing buildings) in the G zone, or working with concentrated salt water in areas outside of the above map, those areas will be temporarily specified as the Y zone.

* The Y zone shown in yellow dotted lines is for when working with concentrated salt water or work related to contamination such as tank transfer lines, and requires G zone equipment during patrols or field surveys in the work planning phase.

Contents List of Good Practice in Radiation Exposure Dose Reduction Measures

No.	Location	Category	Title	Radiation exposure dose equivalent (mSv)			Time (person-days)		Notes
				Before Implementation	After Implementation	Reduction Amount	Before Implementation	After Implementation	
28-01	RB	1	Reducing exposure dose by changing cable storage location	--	--	--	--	--	
28-02-1	RB	4	Decontaminating with remote operation	--	--	--	--	--	
28-02-2	RB	5	Demolishing trusses and removing their debris with remote operation	--	--	--	--	--	
28-03-1	RB	5	Removing small rubble pieces with rubble suction system	3,021	1,278	1,743	8,036	4,088	
28-03-2	RB	5	Using a large rubble (obstructing steel frames) removal device	3,021	1,278	1,743	8,036	4,088	
28-04	RB	5	Surveying the TIP room using a small robot (investigating the state of the inside of the room /measuring radiation exposure dose rate)	--	--	--	--	--	
28-05	RB	5	Surveying MSIV room by inserting long pole into the room (Investigating state of the inside room/measuring dose rate)	--	--	--	--	--	
28-06	RB	6	Preventing dust generation when removing rubble (by spraying mist)	3,021	1,278	1,743	8,036	4,088	
28-07	RB	7	Efficiency improvement of handling suction hose and other assisting operations (improving work method)hose assisting operations.	--	--	--	--	--	
28-08	TB	2	Ensuring distance by using remote-controlled devices	10,079	2,984	--	--	--	
28-09	TB	4	Flushing heater drain (HD) piping (removing radiation source)	10,079	2,984	--	--	--	
28-10	TB	7	Changing access routes to low-radiation exposure dose rate areas	10,079	2,984	--	--	--	
28-11	R	1	Installing prefabricated shelters off-site to simplify site work (changing work location)	--	--	1,069	--	220	
28-12	R	3	Installing shielded booth	--	--	66	--	--	
28-13	R	3	Utilizing shielded boxes from other work (improving work method)	--	--	--	--	--	
28-14	R	7	Clearly display radiation exposure dose at work areas	--	--	--	--	--	
28-15	R	7	Reducing site work by using existing structures (improving work method)	--	--	553	--	--	
28-16	Y	1	Changing excavator bucket installation orientation	--	--	--	--	--	
28-17	Y	3	Shielding surveying machinery control room	--	--	--	--	--	70 → 25 μSv/h
28-18	Y	6	Sheet covering during removal and storage of contaminated soil	--	--	--	--	--	
28-19	G	5	Topographic surveying of inclined ground using drones	13.5	0.5	13	270	24	
28-20	G	7	Providing rest facilities	--	--	--	--	--	
28-21	G	7	Mechanization of mowing work	12	2.5	9.5	240	62	
28-22	G	7	Reducing the amount of protective equipment worn with more detailed site zones	--	--	--	--	--	
28-23	Z	1	Conducting mockup training	--	--	--	--	--	
28-24	Z	2	Changing work location (assembly work at low dose rate areas)	--	--	--	--	--	
28-25	Z	3	Shielding and partitioning transportation routes with a high radiation exposure dose rate	--	--	44.5	--	--	10 → 5 mSv/h
28-26	Z	5	Monitoring using remote-controlled cameras/installing area monitors	--	--	--	--	--	
28-27	Z	6	Preventing contamination from being brought in	--	--	--	--	--	
28-28	Z	7	Preventing internal exposure by wearing two layers of masks	--	--	--	--	--	

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-01
Inside reactor building	RB	RB	1		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Reducing exposure dose by changing cable storage location			
Work location		Inside Unit 3 reactor building			
Overview		Changed from transporting cables for decontamination equipment every day, to storing them inside the building			
Assessment (qualitative/quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Decontamination equipment was carried in and out of buildings everyday, creating the need for assisting operations for cables and other accessories, and increasing the exposure dose.</p> <p>Implementation Details Operation was changed so that decontamination equipment could be stored in the work area inside the building, which reduced the amount of assisting operations when carrying the cables in and out.</p>			
<p>The entrance door could not be closed at night, so the door was adjusted so that it could be left ajar.</p> <p>Before implementation: equipment transportation route</p>					

Good Practice in Radiation Exposure Dose Reduction Measures


Location		Category					No.	28-02-1
Inside reactor building	RB	RB	4	1	Time			
Inside turbine building	TB			2	Distance			
R ZONE	R			3	Shielding			
Y ZONE	Y			4	Removing radiation source			
G ZONE	G			5	Remote-control, robot operation			
Other ()	Z			6	Preventing spread of contamination			
				7	Other			
Title		Decontaminating by remote operation						
Work location		Unit 3 reactor building, 5F (operation floor)						
Overview		Decontamination (removal of radiation sources) was conducted due to the contamination status on the operation floor						
Assessment (<u>qualitative</u> / quantitative)	Effects		Before Implementation	After Implementation				
		Radiation exposure dose (mSv)	--	--				
		Person time (person-days)	--	--				
Good practice description		*Scabblers: process that involves mechanically chipping away the surface of concrete						
Before Implementation		The air dose rates above the operation floor were high and the floor was extremely contaminated, with conditions such that decontamination by workers would result in a high radiation exposure dose.						
Implementation		Decontamination methods were determined based on the contamination status on the floor, and special equipment was selected for each area listed below and used to remove the radiation sources.						
Details								
	(1) $t \geq 600$ slab	(2) $t = 300$ slab	(3) Cask washing area					
Assumed state								
Contamination type	Penetration (epoxy assumed to be damaged)	Penetration	Surface layer					
Material	RC + epoxy	RC + epoxy	Stainless steel					
Surface area	440 m ²	260 m ²	70 m ²					
Decontamination method	Scabblers	Water jet	Chemical (foam-based) decontamination					
Reason for selection	<ul style="list-style-type: none"> • Highest chipping capability • Highest work speed 	<ul style="list-style-type: none"> • Chipping is possible for the floor surface with cracks and some irregularities 	<ul style="list-style-type: none"> • Effectiveness was confirmed particularly for metric material in a decontamination test using actual wastes 					
Expected effects	<ul style="list-style-type: none"> • According to the literature, the radioactivity level at a depth of 5 mm from the surface is about 1/100 of the level at the surface. 	<ul style="list-style-type: none"> • According to the literature, the radioactivity level at a depth of 5 mm from the surface is about 1/100 of the level at the surface (The radioactivity level reduction rate for cracked parts is unknown.) 	<ul style="list-style-type: none"> • The radioactivity level was reduced to 1/10 or less by the decontamination work 					
Typical external appearance of the equipment								

Good Practice in Radiation Exposure Dose Reduction Measures


Location		Category		No.	28-02-2
Inside reactor building	RB	RB	5		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Demolishing trusses and removing their debris by remote operation			
Work location		Unit 3 reactor building, 5F (operation floor)			
Overview		Trusses were demolished and their debris was removed using cranes and heavy demolition equipment with remote operations			
Assessment (<u>qualitative</u> quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good practice description		*Scabblers: process that involves mechanically chipping away the surface of concrete			

Before Implementation The air dose rates above the operation floor were high and the floor was extremely contaminated, with conditions such that demolishing trusses and removing their debris by workers would result in a high radiation exposure dose.


Implementation Details Debris on the operation floor was demolished and removed with a large crawler crane and heavy demolition equipment deployed on a temporary lower platform. Both the crane and the heavy demolition equipment were remotely operated.




Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-03-1		
Inside reactor building	RB	RB	5			1	Time
Inside turbine building	TB					2	Distance
R ZONE	R					3	Shielding
Y ZONE	Y					4	Removing radiation source
G ZONE	G					5	Remote-control, robot operation
Other ()	Z					6	Preventing spread of contamination
						7	Other
Title		Removing small rubble pieces with rubble suction system					
Work location		Unit 1 reactor building, 5F (operation floor)					
Overview		Suctioning and removing small rubble pieces with remote-controlled rubble suction system					
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation			
		Radiation exposure dose (mSv)	*3021	*1278			
		Person time (person-days)	8036	4088			
Good practice description		* Total values of 28-03-1, 28-03-2, and 28-06					
Before Implementation		Rubble varied widely in size, and suctioning rubble with one size of rubble suction system was difficult.					
Implementation Details		A remote-controlled rubble suction system for small rubble pieces was developed and utilized (same as for large rubble removal system)					
<p>(1) Suctioning small rubble pieces using remote-controlled rubble suction system</p> <p>Due to the explosion inside the reactor building after the earthquake, there were countless pieces of small rubble such as concrete strewn across the existing operation floor. This interfered with the installation of mist spray equipment (nozzle unit steel frames), and needed to be removed.</p> <p>Given the high elevation, high radiation exposure dose rate environment, equipment was developed that could suction small pieces of rubble via remote operation. The remote guidance system that was developed while installing the cover was used to suction small pieces of rubble.</p>							
 <p>Duct left/right rotation 90°</p> <p>Duct forward/reverse extension 0.5 m</p>							
▲ Rubble suction system			▲ Rubble suction in progress				



Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category					No.	28-03-2
Inside reactor building	RB	RB	5	1	Time			
Inside turbine building	TB			2	Distance			
R ZONE	R			3	Shielding			
Y ZONE	Y			4	Removing radiation source			
G ZONE	G			5	Remote-control, robot operation			
Other ()	Z			6	Preventing spread of contamination			
				7	Other			
Title		Using a large rubble (obstructing steel frames) removal device						
Work location		Unit 1 reactor building, 5F (operation floor)						
Overview		Large rubble (obstructing steel frames) removal equipment was developed, and used via remote operation						
Assessment (<u>qualitative/quantitative</u>)	Effects		Before Implementation	After Implementation				
		Radiation exposure dose (mSv)	*3,021	*1,278				
		Person time (person-days)	8,036	4,088				
Good Practice description		* Total values of 28-03-1, 28-03-2 and 28-06						
Before Implementation		Rubble varied widely in size, and removing rubble with one size of rubble removal equipment was difficult.						
Implementation Details		Remote-controlled rubble removal equipment for large rubble was developed and utilized.						
<p>(2) Removing large rubble pieces (obstructing steel frames) using remote-controlled rubble removal equipment</p> <p>In addition to small rubble pieces across the existing operation floor steel frame, large rubble pieces such as bent steel frames and piping caused other objects to catch and interfere with operations.</p> <p>Small rubble removal equipment with cutting and pinching functions was developed, and used to remove large rubble pieces via remote operations similarly to suction of small rubble pieces.</p>								
 <p>▲ Equipment overview (used by hoisting with crane) Weight: approx. 18 t Drive unit: Hydraulic</p>		<p>Small cutter ▼</p> 						

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-04
Inside reactor building	RB	RB	5		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Surveying the TIP room using a small robot (investigating the state of the inside of the room /measuring radiation exposure dose rate)			
Work location		Unit 1 reactor building, 1F, TIP room			
Overview		The state inside the TIP room was unknown, so a small robot was used to survey the area			
Assessment (<u>qualitative</u> quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation There was a high possibility of a high radiation exposure dose rate inside the TIP room, so it was not possible for workers to enter the area, and its state remained unknown.</p> <p>Implementation Details A hole was drilled in a wall and a small robot moved inside to measure the environment radiation exposure dose rate and also survey the state inside the TIP room. Workers operated the robot remotely from a nearby area with a low radiation exposure dose rate, which prevented any unnecessary exposure.</p>			
<div style="border: 1px solid black; padding: 5px; margin-bottom: 5px;"> The dose rate in the room atmosphere is unknown </div> <div style="border: 1px solid black; padding: 5px;"> A hole is drilled in a wall to gain access to the inside of the room </div>		<div style="border: 1px solid black; border-radius: 15px; padding: 10px; display: inline-block;"> <p style="color: red; margin: 0;">Survey using small remotely-operated robot</p> <ul style="list-style-type: none"> ▪ Workers operated the robot from an area with a low radiation exposure dose ▪ The robot is small enough to be able to enter the room through a small hole </div>			
 <p>Robot operated remotely from low radiation exposure dose area</p>		 <p style="text-align: center;">Remote-operated robot (optical camera, dosimeter)</p>			


Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-05
Inside reactor building	RB	RB	5		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Surveying MSIV room by inserting long pole into the room (investigating state of the inside room/measuring dose rate)			
Work location		Unit 1 reactor building, 1F, MSIV room			
Overview		The state inside the MSIV room was unknown, so a 3D laser scanner was used to survey the area			
Assessment (<u>qualitative</u> / quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation A high radiation exposure dose rate was expected inside the MSIV room, so it was not possible for workers to enter the area, and its state remained unknown.</p> <p>Implementation Details A long pole was used to measure the radiation exposure dose rate and survey the state inside the MSIV room from a low radiation exposure dose rate area.</p>			
<p>Radiation exposure dose rate inside the room unknown</p> <p>High radiation exposure dose around the room entrance</p> <p>Entrance to the room is approximately 4 m from the floor</p>		<p>The room is surveyed by inserting a long pole into the room</p> <ul style="list-style-type: none"> The surveying equipment was installed at the end of the long pole. Exposure of the worker is reduced by the long distance between end of the pole and the high dose entrance. 			
<p>Pole manipulated from low radiation exposure dose area (2 mSv/h)</p> 					
		 <p>External appearance of the 3D laser scanner</p>			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-06
Inside reactor building	RB	RB	6		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Preventing dust generation when removing rubble (by spraying mist)			
Work location		Unit 1 reactor building, 5F (operation floor)			
Overview		A mist was sprayed when removing rubble			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	*3,021	*1,278	
		Person time (person-days)	8,036	4,088	
Good Practice Description		* Total values of 28-03-1, 28-03-2 and 28-06			
Before Implementation		There was the risk of dust being generated when removing rubble from the operation floor.			
Implementation Details		To prevent dust being generated when removing rubble, equipment was installed to spray mist.			
<Mist spraying equipment>					
After the building cover was demolished, the rubble pieces that had built up on the reactor building operation floor were removed.					
To limit any potential radioactive dust from spreading during the removal of rubble, mist spraying equipment was installed on the existing operation floor steel frame.					
Basic plan					
East side		West side		Image of nozzle unit steel frame and spray	
▲ Mist spraying equipment (nozzles) layout plan, spraying pattern		▲ Image of nozzle unit steel frame and spray			



Good Practice in Radiation Exposure Dose Reduction Measures;

Location		Category		No.	28-07
Inside reactor building	RB	RB	7		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Efficiency improvement of handling suction hose and other assisting operations (improving work method)			
Work location		Unit 3 reactor building			
Overview		Mounting the suction hoses of decontamination equipment onto trolleys helped to improve suction hose assisting operations			
Assessment (<u>qualitative</u> quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Extra assisting operations for the suction hoses when transporting decontamination equipment were resulting in increased exposure dose.</p> <p>Implementation Details The suction hoses of decontamination equipment were mounted onto trolleys with casters to improve assisting operations.</p>			
 <p>Suction hose (100 m) and hose-assisting worker</p>					
					
Work in progress 1		Suction hoses, trolleys with casters			
Work in progress 2		Work in progress 3			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-08
Inside reactor building	RB	TB	2		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Ensuring distance by using remote-controlled devices			
Work location		Unit 1 turbine building, 1F			
Overview		A remote-controlled hydraulic cutter was used to remove impeding rubble in the floor drain pit in the basement of turbine building 1F			
Assessment (<u>qualitative/quantitative</u>)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	*10,079	*2,984	
		Person time (person-days)	--	--	
Good Practice Description		* Total values of 28-08 to 10			
Before Implementation	The basement of the turbine building was an area with a high radiation exposure dose rate, and workers removing impeding objects were expected to be subjected to a high exposure dose.				
Implementation Details	A remote-controlled hydraulic cutter was used and controlled by workers from areas with a low radiation exposure dose rate on 1F. Additional shielding was installed on the handrail where the workers were located to reduce the environment radiation exposure dose rate there.				
<p>Additional shielding installed on handrails</p>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-09
Inside reactor building	RB	TB	4		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Flushing heater drain (HD) piping (removing radiation source)			
Work location		Unit 1 turbine building, 1F			
Overview		The heater drain (HD) piping that was a radiation source was flushed with cleaning water to remove the radiation source			
Assessment (qualitative/ <u>quantitative</u>)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	*10,079	*2984	
		Person time (person-days)	--	--	
Good Practice Description		* Total values of 28-08 to 10			
Before Implementation	The unit 1 condenser (including the heater drain piping) was verified to be a high dose radiation source due to the stagnant water stored after the earthquake, which could subject workers to a high exposure dose.				
Implementation Details	The water within the condenser and heater drain piping was drained and diluted.				
	Step 1: install temporary pump inside condenser.				
	Step 2: partially drain stagnant water within condenser.				
	Step 3: inject diluted water from the heater drain piping.				
	Step 4: drain water within condenser again.				
	Step 5: repeat steps 3 and 4 several times.				
 <p>14 to 61 mSv/h * Trench top</p> <p>Condenser Condenser Heater drain piping Floor drain sump D/G T.P.443 T.P.543 OP.490b Bamboo T.P.3443</p> <p>Work area (plan)</p> <p>Unit 1 turbine building floor plan</p>		 <p>Basement 1F intermediate level T.P.3443 (O.P.4900) Basement 1F T.P.443 (O.P.1900)</p> <p>Inject diluted water from heater Heater Heater drain piping To building stagnant water Condenser Step 2, 4 Step 1 Current water level Temporary pump Hot well top plate</p> <p>Radiation source</p> <p>Work image (Unit 1 turbine building cross-sectional plan)</p>			
<p><Note> It is vital to verify the location of the radiation source and treatment location the water used for flushing. (The treatment location could be subjected to a high radiation exposure dose rate)</p>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-10
Inside reactor building	RB	TB	7	1	
Inside turbine building	TB			2	
R ZONE	R			3	
Y ZONE	Y			4	
G ZONE	G			5	
Other ()	Z			6	
				7	

Title Changing access routes to low radiation exposure dose rate areas

Work location Unit 1 turbine building, 1F


Overview An area with a low radiation exposure dose rate was selected for the route to work areas to reduce exposure dose when moving

Assessment (qualitative/ <u>quantitative</u>)	Effects		Before Implementation	After Implementation
		Radiation exposure dose (mSv)	*10,079	*2,984
		Person time (person-days)	--	--

Good Practice Description * Total values of 28-08 to 10

Before Implementation The route for moving to work areas included sections with a high radiation exposure dose rate, and there was the possibility of increased exposure dose while moving.

Implementation Details Routes with a high radiation exposure dose rate were avoided, and an area with a low radiation exposure dose rate selected as the access route to work areas to reduce the exposure dose when moving. Workers were also informed of the change.



<Note> Verifying the access route by measuring the ambient radiation exposure dose rate everyday is important.


Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-11
Inside reactor building	RB	R	1	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Installing prefabricated shelters off-site to simplify site work (changing work location).			
Work location		Around the Unit 3 turbine building backwashing valve pit			
Overview		Prefabricated shelters were assembled off-site while installing the cover to the backwashing valve pit to simplify the site work and shorten time			
Assessment (qualitative/ <u>quantitative</u>)	Effects		Reduction Amount		
		Radiation exposure dose (mSv)	1069		
		Person time (person-days)	220		
Good Practice Description		<p>Before Implementation The backwashing valve pit had an ambient radiation exposure dose rate of around 2.9 mSv/h due to the surrounding rubble, and there was the possibility of a high radiation exposure dose while installing the pit cover.</p> <p>Implementation Details Cover materials were prefabricated (assembled) off-site to be moved and installed as assembled, in order to simplify work around the backwashing valve pit and shorten the time required.</p>			
		<p>(1) Roof and pillar assembled and temporarily mounted off-site (outside control zones)</p> <p>(2) This achieved the same effects as the mockup.</p> <p>(3) Transported cover materials to the site</p>			
					
					
		Off-site work (photos)			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-12
Inside reactor building	RB	R 3	1	Time	
Inside turbine building	TB		2	Distance	
R ZONE	R		3	Shielding	
Y ZONE	Y		4	Removing radiation source	
G ZONE	G		5	Remote-control, robot operation	
Other ()	Z		6	Preventing spread of contamination	
			7	Other	
Title		Installing shielded booth			
Work location		Units 1 to 4 seaside area			
Overview		A shielded booth was installed for management staff to reduce their exposure dose			
Assessment (<u>qualitative/quantitative</u>)	Effects			Reduction Amount	
		Radiation exposure dose (mSv)		66	
		Person time (person-days)		--	
Good Practice Description		<p>Before Implementation Management staff were always monitoring work from an on-site location. Staying in an area with a relatively low radiation exposure dose rate for a long period of time increased their exposure dose.</p> <p>Implementation Details A shielded booth was installed for management staff, where they could spend time for duties other than site management, to reduce their exposure dose.</p> <p>1. A lead-shielded booth was installed for management staff where they could spend 50% of their work time (effect of lead shielded booth: approximately 50%)</p> <p>2. Expected effects</p> <p>(1) Workers: 2 people × 100 days = 200 person-days</p> <p>(2) Work environment radiation exposure dose rate: amount of reduction 20 person-mSv</p> <p>Before: 0.10 mSv/h 4 hours × 200 person-days = 80 person-mSv</p> <p>After: (0.10 mSv/h × 2 hours) + (0.05 mSv/h × 2 hours) × 200 person-days = 60 person</p>			
		 <p style="text-align: center;">Lead-shielded standby booth</p>			
<div style="border: 1px solid blue; padding: 5px;"> <p><Note> It is important to determine and install a shielded booth commensurate with the number of workers who will be using it.</p> </div>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-13		
Inside reactor building	RB	R	3			1	Time
Inside turbine building	TB					2	Distance
R ZONE	R					3	Shielding
Y ZONE	Y					4	Removing radiation source
G ZONE	G					5	Removing radiation source
Other ()	Z					6	Removing radiation source
						7	Other
Title		Utilizing shielded boxes from other work (improving work method)					
Work location		Outside Unit 3 reactor building					
Overview		Utilizing shielded boxes from other work (improving work method)					
Assessment (<u>qualitative</u> quantitative)	Effects		Before Implementation	After Implementation			
		Radiation exposure dose (mSv)	--	--			
		Person time (person-days)	--	--			
Good Practice Description		<p>Before Implementation Temporary shielded booths were installed, however their shielding was not as effective as expected due to a high radiation exposure dose from above.</p> <p>Implementation Details Work processes were adjusted so that box culverts near the work area that had been installed and used for other work could be utilized as shared evacuation shelters. A daily usage schedule was also created to avoid crowding.</p>					
<p>Before implementation No shielding in ceiling of temporary shielded booth.</p>							
<p>After implementation</p>							

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-14
Inside reactor building	RB	R	7	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other

Title Clearly display radiation exposure dose at work areas

Work location Side of turbine building

Overview Show high-radiation exposure dose positions in work areas to make workers aware of the radiation exposure dose rate.

Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation
		Radiation exposure dose (mSv)	--	--
		Person time (person-days)	--	--

Good Practice Description

Before Implementation No display of radiation exposure dose, meaning there was a possibility that workers could be subjected to unnecessary exposure in high-radiation exposure dose locations.

Implementation Details High-radiation exposure dose areas are clear, meaning low-radiation exposure dose areas could be utilized to reduce workers' exposure dose.

Example display

The dose equivalent here is






A high-radiation exposure dose area. Caution!

The radiation exposure dose equivalent here is



Keep time here at a minimum!

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-15
Inside reactor building	RB	R	7		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Reducing site work by using existing structures (improving work method)			
Work location		Around the Unit 3 turbine building backwashing valve pit			
Overview		Instead of making a foundation on which to install the cover material, the pit enclosure was used as the foundation (improving work method)			
Assessment (qualitative/ <u>quantitative</u>)	Effects		Reduction Amount		
		Radiation exposure dose (mSv)	553		
		Person time (person-days)	--		
Good Practice Description		<p>Before Implementation The backwashing valve pit had an ambient radiation exposure dose rate of up to 2.9 mSv/h due to the surrounding debris, and there was the possibility of a high radiation exposure dose while making the foundation for installing the pit cover.</p> <p>Implementation Details The existing backwashing valve pit enclosure was used as the foundation to install the cover material, eliminating the need to construct a foundation (improving work method).</p>			
<p>Directly place the cover on the pit enclosure</p>   					


Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category			
Inside reactor building	RB	Y	1	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
				No.	28-16
Title		Changing excavator bucket installation orientation			
Work location		Slope on site			
Overview		Excavator buckets were installed in reverse to normal when stripping the soil, to improve work efficiency			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Using ordinary excavators to strip the soil on the slope was expected to result in poor work efficiency and take longer.</p> <p>Implementation Details The excavator bucket was installed in reverse to make it easier to strip soil from the slope.</p>			
		<p>The bucket was modified to make stripping soil from the slope easier. Work time was reduced by using an excavator suited to site conditions.</p>			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-17
Inside reactor building	RB	Y	3		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other ()	Z			6	Preventing spread of contamination
				7	Other
Title		Shielding surveying machinery control room			
Work location		Unit 4 Seaside area			
Overview		Shielding methods developed using lead wool mats			
Assessment (qualitative quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation The dose rate in the surveying machinery control room was 70 μSv/h due to γ rays from the ground and turbine side.</p> <p>Implementation Details Lead wool mats, crushed stone and iron plates were installed in the direction of each radiation source (turbine side and ground) to provide shielding.</p>			
					
<ul style="list-style-type: none"> - Installing lead wool mat shielding against radiation from the turbine building reduced the ambient radiation exposure dose rate from 70 μSv/h \rightarrow 25 μSv/h (by approximately 60%). - Shielding against radiation from the ground was achieved using crushed stone and iron plates. 					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-18
Inside reactor building	RB	Y 6	1		
Inside turbine building	TB		2	Distance	
R ZONE	R		3	Shielding	
Y ZONE	Y		4	Removing radiation source	
G ZONE	G		5	Remote-control, robot operation	
Other ()	Z		6	Preventing spread of contamination	
			7	Other	
Title		Sheet covering during removal and storage of contaminated soil			
Work location		Slope on site			
Overview		Stripped soil was covered by sheets when placing the soil in sandbags			
Assessment (<u>qualitative</u> / quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Soil stripped using an excavator bucket was spreading contamination when being placed in bags, as the contaminated soil scattered around the sandbags.</p> <p>Implementation Details A sheet was placed under the sandbag filling equipment to prevent contaminated soil from scattering.</p>			
 <p>Wood was used to prevent sandbags from being damaged due to rocks or other objects</p>		 <p>The sheet under the sandbag equipment helped prevent the spread of contamination and damage to sandbags</p>			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-19	
Inside reactor building	RB	G 5	1			Time
Inside turbine building	TB		2			Distance
R ZONE	R		3			Shielding
Y ZONE	Y		4			Removing radiation source
G ZONE	G		5			Remote-control, robot operation
Other ()	Z		6			Preventing spread of contamination
			7			Other
Title		Topographic surveying of inclined ground using drones				
Work location		Sloped areas on site				
Overview		Surveying work conducted prior to repairing slopes was changed from manual labor to drone aerial photos				
Assessment (<u>qualitative/quantitative</u>)	Effects		Before Implementation	After Implementation		
		Radiation exposure dose (mSv)	13.5	0.5		
		Person time (person-days)	270	24		
Good Practice Description		<p>Before Implementation Safety rope anchors were installed so that numerous staff could work safely on the slope to conduct surveys. (Work period...approximately 30 days)</p> <p>Implementation Details The use of drones meant that surveying control points and operating the drones was required, resulting in shorter work period. (Work period...approximately 5 days)</p>				
						
Drone main unit		Controller				

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-20
Inside reactor building	RB	G 7	1		
Inside turbine building	TB		2	Distance	
R ZONE	R		3	Shielding	
Y ZONE	Y		4	Removing radiation source	
G ZONE	G		5	Remote-control, robot operation	
Other ()	Z		6	Preventing spread of contamination	
			7	Other	
Title		Providing rest facilities			
Work location		1F off-site area			
Overview		Providing rest facilities near work location			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation The work area was located off-site on 1F; however, the rest area was on-site on 1F, with the distance resulting in exposure doses.</p> <p>Implementation Details Rest facilities were installed near work location.</p>			
					
<p align="center"><u>Break room</u></p>		<p align="center"><u>Body survey room</u></p>			
		<p align="center"><u>Air-conditioning and local ventilation</u></p>			

Good Practice in Radiation Exposure Dose Reduction Measures


Location		Category		No.	28-21
Inside reactor building	RB	G 7	1		
Inside turbine building	TB		2	Distance	
R ZONE	R		3	Shielding	
Y ZONE	Y		4	Removing radiation source	
G ZONE	G		5	Remote-control, robot operation	
Other ()	Z		6	Preventing spread of contamination	
			7	Other	
Title		Mechanization of mowing work			
Work location		1F on-site flat and sloped land			
Overview		Machines are used for mowing work on the site that was previously cut by hand			
Assessment (qualitative/ <u>quantitative</u>)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	12	2.5	
		Person time (person-days)	240	62	
Good Practice Description		<p>Before Implementation Motorized mowers were used to cut grass by hand.</p> <p>Implementation Details A mower unit was mounted to an excavator and used to cut the grass, reducing labor hours.</p>			
					
Mowing on flat land		Mowing on sloped area			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		G 7	Category	
Inside reactor building	RB		1	Time
Inside turbine building	TB		2	Distance
R ZONE	R		3	Shielding
Y ZONE	Y		4	Removing radiation source
G ZONE	G		5	Remote-control, robot operation
Other ()	Z		6	Preventing spread of contamination
			7	Other
No. 28-22				
Title		Reducing the amount of protective equipment worn with more detailed site zones		
Work location		All yard green zones		
Overview		As part of decontamination efforts across the site, zones were classified into high-dose areas and other areas		
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation
		Radiation exposure dose (mSv)	--	--
		Person time (person-days)	--	--
Good Practice Description				


Before Implementation Contamination categories were not assigned thoroughly for required work equipment, resulting in workers wearing more equipment than necessary, increasing their workload and reducing work efficiency.

Implementation Details Categorizing the work equipment for each contamination zone reduced the protective equipment and workload of workers, improved work efficiency and reduced their exposure dose.



R zone (Anorak areas)	Y zone (Coverall areas)	G zone (Regular uniform areas)
Full-face mask 	Full-face mask *1 *2 Or half-face mask 	Disposable dust mask
Anorak over coverall 	Coverall 	Regular uniform *3 On-site uniform
Or coverall over coverall		

*1 For work performed inside buildings of Units 1-4 and surrounding buildings, including water treatment facilities such as multi-nuclide removal facilities (excluding observation visits), full-face masks are to be worn.
 *2 For work performed around tanks containing contaminated water, for example, concentrated salt water or strontium treated water (excluding work that does not involve the handling of concentrated salt water, field surveys in the work planning phase, patrolling, observation visits, etc.), and work that involves the handling of transport lines to tanks, full-face masks are to be worn.



● After the new zoning application, the average daily use rate of full-face masks has decreased from about 66% to about 47% and the average daily use rate of disposable dust masks (DS2) has increased from about 28% to about 48%.

● These changes indicate reductions in protection level that equipment must provide from full-face masks to DS2 masks. (This resulted in better work efficiency)

Full-face mask, half-face mask, and DS2 usage

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-23
Inside reactor building	RB	Z	1	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (main process building)	Z			6	Preventing spread of contamination
				7	Other
Title		Conducting mockup training			
Work location		Main processing building route			
Overview		A situation similar to the actual working environment was reproduced to reduce the operation time			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Shortening work time is essential for reducing exposure dose.</p> <p>Implementation Details Mockup training of the actual area was conducted to help shorten work time.</p>			
<h2>Mockup training</h2> <ul style="list-style-type: none"> • <u>A situation similar to the actual working environment was reproduced</u> to reduce the operation time. 					
					
<p><Note> It is vital to reproduce all aspects, such as worker assignment, movement, equipment handling processes and worn protective equipment as close as possible to the actual work.</p>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-24
Inside reactor building	RB	Z	2	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (main process building)	Z			6	Preventing spread of contamination
				7	Other
Title		Changing work location (assembly work at low dose rate areas)			
Work location		Main processing building route			
Overview		Equipment was assembled in areas with a low radiation exposure dose, and transported and installed with a crane after assembly to help reduce the exposure dose			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice					

Before Implementation The equipment was installed in a high radiation exposure dose area, and assembling the equipment there would result in a high exposure dose.

Implementation Details Equipment was assembled in areas with a low radiation exposure dose, and transported and installed with a crane after assembly.

Assembly work at low dose rate areas

• Assembly of the pump unit takes time (8 days). From the construction planning stage, a method to install the unit after assembling it in a low dose rate area was considered and implemented.



Assembled in a low dose rate area
(0.07 mSv/h)



Moved using a crane




Installed in a high dose rate area
(5 mSv/h)


Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-25
Inside reactor building	RB	Z	3		
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (main process building)	Z			6	Preventing spread of contamination
				7	Other
Title		Shielding and partitioning transportation routes with a high radiation exposure dose rate			
Work location		Main processing building route			
Overview		Shielding in high radiation exposure dose rate routes, partitioning of high radiation exposure dose rate areas and clearly displaying the direction of movement were used to help reduce exposure doses as much as possible while moving			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	44.5	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Shielding was required against the γ radiation source at the center of the pit area.</p> <p>Implementation L-shaped shielding was installed along routes to halve the ambient radiation exposure dose rate, and partitioning and directions were displayed clearly (visualization) to prevent accidental entry into high radiation exposure dose areas.</p> <p>(1) L-shaped temporary shielding installed Dose rate contribution from the main radiation source at the central part of the pit was reduced (10.0 mSv/h → 5.0 mSv/h)</p> <p>L-shaped temporary shielding</p>  <p>(2) Travel path sectioned (visualized)</p> <ul style="list-style-type: none"> To prevent accidental travel through high dose rate areas, the <u>travel path was sectioned using tapes</u> To prevent unnecessary exposure while travelling, <u>travel direction was clarified using arrows</u>  			

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category			
Inside reactor building	RB	Z	5	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (main process building)	Z			6	Preventing spread of contamination
				7	Other
				No.	28-26
Title		Monitoring using remote-control cameras/installing area monitors			
Work location		Main processing building route			
Overview		Instead of supervisors attending worksites to give work instructions, remote-control cameras were used to provide instructions and monitor readings from the area remotely			
Assessment (qualitative) (quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Supervisors used to attend worksites to give work instructions, resulting in high exposure doses amongst supervisors.</p> <p>Implementation Details To reduce the amount of exposure for supervisors, work instructions were provided from the control office outside the building, and remote monitoring cameras and radiation monitors installed.</p>			
<h2>Remote-control camera/area monitor</h2> <div style="display: flex; justify-content: space-around;"> <div style="text-align: center;">  <p>Installation of remote-control cameras</p> </div> <div style="text-align: center;">  <p>Installation of area monitor</p> </div> <div style="text-align: center;">  <p>Checking the work site through a monitor screen</p> </div> </div>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category		No.	28-27
Inside reactor building	RB	Z	6	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (unit 5, 6 service buildings)	Z			6	Preventing spread of contamination
				7	Other
Title		Preventing contamination from being brought in			
Work location		Unit 5, 6 service buildings (S/B)			
Overview		The S/Bs were in low-contamination areas, and measures were introduced to prevent contamination being brought in as well as to ensure thorough cleaning, to help improve work efficiency and reduce work equipment			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation: Access to the S/Bs required a change of boots to prevent outside contamination being brought in; however, there were concerns about the possibility of outside contamination being brought in due to the major increase in number of workers accessing the building.</p> <p>Implementation Details: Changing boots and thorough cleaning/partitioning was used to prevent contamination being brought in.</p>			
<div style="border: 1px solid black; border-radius: 15px; padding: 5px; display: inline-block;">Reduce physical load</div>		<ul style="list-style-type: none"> Prevented contamination being brought in, and reduced the work equipment for installing new equipment (using N95 dust mask) Installed a rest area inside work area (on-site cooler) <div style="border: 1px solid black; padding: 2px; margin-top: 5px;">Effects: construction proceeded during summer, but no workers reported heat stroke</div>			
<div style="border: 1px solid black; border-radius: 15px; padding: 5px; display: inline-block;">Prevent bodily contamination</div>		<ul style="list-style-type: none"> Changing boots and thorough cleaning/partitioning <div style="border: 1px solid black; padding: 2px; margin-top: 5px;">Effects: no major bodily contamination reported during the construction period</div>			
<div style="border: 1px solid black; border-radius: 15px; padding: 5px; display: inline-block;">Preventing spread of contamination</div>		<ul style="list-style-type: none"> Changing boots and thorough cleaning/partitioning Prevented spread of contamination with clean house and local ventilation <div style="border: 1px solid black; padding: 2px; margin-top: 5px;">Effects: no spread of contamination throughout work area, no returning for decontamination required</div>			
<div style="text-align: center;">  <p style="text-align: center;">Entry route</p> </div> <div style="display: flex; justify-content: space-around; margin-top: 10px;"> <div style="text-align: center;">  <p>Tool checks</p> </div> <div style="text-align: center;">  <p>Physical checks</p> </div> <div style="text-align: center;">  <p>Cleaning routes</p> </div> </div> <div style="border: 1px solid black; padding: 5px; margin-top: 10px; text-align: center;"> <p><Note> Checking by verifying the contamination every day is important.</p> </div>					

Good Practice in Radiation Exposure Dose Reduction Measures

Location		Category			
Inside reactor building	RB	Z	7	1	Time
Inside turbine building	TB			2	Distance
R ZONE	R			3	Shielding
Y ZONE	Y			4	Removing radiation source
G ZONE	G			5	Remote-control, robot operation
Other (main process building)	Z			6	Preventing spread of contamination
				7	Other
				No.	28-28
Title		Preventing internal exposure by wearing two layers of masks			
Work location		Main processing building route			
Overview		A full-face mask and hooded mask were required to prevent internal exposure of workers			
Assessment (qualitative/ quantitative)	Effects		Before Implementation	After Implementation	
		Radiation exposure dose (mSv)	--	--	
		Person time (person-days)	--	--	
Good Practice Description		<p>Before Implementation Wearing a full-face mask to work sites resulted in high-level contamination collected in dust filters, introducing the risk of internal exposure.</p> <p>Implementation Details To prevent internal exposure, workers were required to wear a hooded mask over the full-face mask in a two-layer arrangement.</p>			
<h2>Wearing two layers of masks (full-face and hooded masks)</h2> <ul style="list-style-type: none"> To ensure the prevention of internal exposure, a dual-filter system was adopted (full-face mask filter + AP-60 filter) 					
<p>Blower with filter (AP-60)</p>		+		<p>Special hooded mask (HD-EFS)</p>	
		<p>AP-60 equipped</p>			

Column

- Greater sense of safety amongst workers -

"Safety First/Measures to Reduce Exposure...OK!"

I had a weird sense when I first saw this photo. "What's that for?"
After thinking about it for a while, I saw that this was actually an act of love.
"What were they thinking when they wrote it? And who did they write it for?"
Loving your home town, your company, your friends, and of course your family..."
I'm sure that all of these apply.

The photo also indicates how difficult this decades-long process will be to achieve
"without injury, without exposure."
The only response is... "Safety First!"

(by S.K)



Safety First

Safety First
Measures to
Reduce
Exposure...OK!!





1F - Unit 1 Reactor Building 5F Suction of rubble pieces such as roof blocks using large rubble suction machine

Source: Shimizu Corporation

Good Practices in Radiation Exposure Dose Reduction Measures

Published February 2017

Commissioned by the Ministry of Health, Labour and Welfare in FY2016

"Project to Enhance the International Transmission of Radioactivity-Related Information on the Workers at TEPCO Holdings' Fukushima Daiichi Nuclear Power Plant"

Trustee: Japan Environment Research Co., Ltd.